

*Geert Cortenbosch*

# **Establishing decommissioning plans and the decommissioning of the fuel facility FBFC in Belgium**



filiaal van het FANC | filiale de l'AFON



# Summary

- The FBFC Decommissioning Project
  - History
  - Licensing procedure for decommissioning
  - Content of demand for license for decommissioning and dismantling
  - Decommissioning license
  - Decommissioning and dismantling phase
  - Waste Management Program



# History FBFC International

- Clients:
  - F: EDF
  - B: ELECTRABEL/TRACTEBEL
  - D: All producers of electricity
  - Others: Sweden, Switzerland, S-Africa and Japan

Tablets: from 14x14 to 18x18 UO<sub>2</sub> and 10x10 tot 18x18 Gd<sub>2</sub>O<sub>3</sub>


Fuel elements: from 8x8 to 10x10 MOX and 14x14 to 18x18 MOX en UO<sub>2</sub>

- FBFC exists since 1961

## Activities in the past

- UO<sub>2</sub>
  - tablets, pins, elements and frames
- Gadolinium
  - tablets and pins
- MOX
  - elements
- Small components
  - stoppers and springs for fuel pins
- R & D oxides

# FBFC International - Dessel



# Licensing procedure for decommissioning

- Based on requirements of FANC
- Based on:
  - IAEA Safety Requirements: Predisposal Management of Radioactive Waste, including Decommissioning (WS-R-2)
  - IAEA Safety Guides:
    - Decommissioning of Nuclear Power Plants and Research Reactors (WS-G-2.1)
    - Decommissioning of Medical, Industrial and Research Facilities (WS-G-2.2)
    - Decommissioning of Nuclear Fuel Cycle Facilities (WS-G-2.4)

# Content of demand for license for decommissioning and dismantling

- Introduction
- Description of the installation
- Radiological and toxic inventory
- Dismantling strategy
- Purpose, dismantling alternatives, safety principals and criteria, destination of the site, ...
- Project Management
- Personnel, Documentation, Financing
- Quality System



# Content of demand for decommissioning and dismantling

- Dismantling activities
  - Planning, decontamination and dismantling techniques, release, re-use of materials,...
  - Safety Analysis
  - ALARA study
  - Safety systems, Incident Analysis, Criticality, Industrial Safety, Emergency Planning, Security,...
  - Environmental Report

# Decommissioning license

- License conditions

- Specific procedures needed (release of waste, dismantling techniques, ...)
- Safety evaluation report / Decommissioning plan / Technical report
- QS system
- Procedures and instructions / ALARA study
- Inventory of radioactive waste
- Inspection program
- Risk analysis (for new dismantling techniques)
- Dose registration
- Operational experience feedback system
- Methodology and results of final characterisation

## Decommissioning license

- License received for decommissioning of buildings 1 (lab), 2 (Gado), 3 (ARIEL) and 5M (MOX) on Dec 8, 2010
- License for decommissioning of building 5 (Uranium) received end of 2013

## Since 2012

- Stop Uranium / gadolinium production in 2012;
- Assembly of MOX fuel elements stopped in 2015
- Production of stoppers and springs for fuel pins (stopped end of 2012)
- From April 2012 ~ 30 FBFC staff members on site (for safety, security, MOX production and dismantling activities) + subcontractors

## Dismantling activities (status October 2016)

- Buildings 1, 2, 3 and 5 will be demolished
  - Buildings 1 & 2 (decommissioning started end of 2012 and will be completed beginning of 2017)
  - Building 3 (demolished in December 2015, decontamination of foundations between December 2015 and April 2016)
  - Building 5 (decommissioning started end of 2013 and will be finished in 2017)
  - Building 5M will probably be reused, but MOX installations will be dismantled in 2017
- Decommissioning of ARIEL Water Treatment installation in 2017
- UO<sub>2</sub> powder and last 25 spare MOX rods evacuated in 2016
- FBFC site will probably be reused after release in 2018

## Dismantling

- Is done by subcontractors
- Monthly follow-up visits by Bel V
- No real anomalies during decommissioning activities, except:
  - one fire incident in August 2015 in a filterinstallation,
  - overflow of a watertank with slightly uranium contaminated water in October 2016,
- Some sand contaminations found in building 3 and in canals on and around the FBFC site + contaminations of surfaces in buildings 1, 2, 3 and 5

# Data and information during decommissioning on the FBFC site

- 920 tons of equipment to evacuate
  - of which 655 tons contaminated equipment
- 35000 m<sup>2</sup> of surfaces to be released
  - of which 25000 m<sup>2</sup> to decontaminate
- 3400 m<sup>3</sup> of waste to treat
  - 3050 m<sup>3</sup> of ground and sand
  - 100 m<sup>3</sup> of peeled products (crust)
  - 250 m<sup>3</sup> of bricks and pipings



# Contaminated areas: Equipments

- Metals
  - For melting at Studsvik (till 2015) and Energy Solutions
  - Non accepted alloys to NIRAS/ONDRAF (Belgian Agency for Radioactive Waste and Enriched Fissile Materials)
- Verification of the contaminations of the equipments
  - Surface
    - $> 0,04 \text{ Bq/cm}^2 \alpha \rightarrow$  to NIRAS
  - Mass
    - $> 1 \text{ Bq/g } \alpha \rightarrow$  to NIRAS



# Contaminated areas: Buildings

- Floors, walls, ceilings, beams
  - Cleaning by aspiration of the dust
  - Removal of one layer ~ 3 mm  
(for example by peeling)
  - Verification of the contamination  
(double measurement)
    - $\leq 0,04 \text{ Bq/cm}^2$  (alpha)
    - $\leq 0,4 \text{ Bq/cm}^2$  (beta)
  - Verification of the waste drums using gamma spectrometry
    - $< 1 \text{ Bq/g}$  (total activity = U-234 + U-235 + U-238)
    - Determination of the U-235 activity with gamma spectrometry (ISOCS - In Situ Object Counting System) and calculation of the U-234 and U-238 activities taking into account the mean isotopic vector



**ISOCS**

# Excavation and decontamination of the pipes



# Used decontamination techniques



Decontamination of the floor



Measurement of contaminated bricks



Removal of pipes and contaminated ground

# Site

- Methodology for the release of the site
  - $< 1$  Bq/g (total activity = U-234 + U-235 + U-238)
  - Maximum dose impact for the most exposed person: 10  $\mu$ Sv per year
  - Sampling: if Activity  $> 1$  Bq/g  $\rightarrow$  excavation
  - Measurement of the samples: determination of the U-235 activity with gamma spectrometry and calculation of the U-234 and U-238 activities taking into account the mean isotopic vector

# Canals

- Same methodology for the canals




# Waste Management Program

- All materials are selectively collected in waste categories
- Specific waste drums are used to collect the waste
- All drums are radiologically characterised
- The results of the characterisation determine the removal paths of the material
- All information of each drum is saved in a data management system

# Contaminated soil

- Contaminated soil sorting unit
  - Plastic scintillator
  - 10 tons per hour
  - < 1 Bq/g, 1 tot 10 Bq/g and > 10 Bq/g



THANK YOU FOR YOUR ATTENTION